

3370 6th Ave, Troy - Scope of Work

Handicap Access Ramp

- Remove existing wooden stairs and landing in their entirety from 6th Ave side entry vestibule, chain link fence along concrete window well in front of side entry, and any debris on lawn directly in front of side entry.
- Install new approx. 5' x 30' x 4" concrete ramp at 1:12 slope on concrete grade.
- New landing at 30' from entry. **SEE PLANS FOR DETAIL!**
- Provide and install new 1 1/2" metal railings painted black and set in PVC or stainless steel sleeves both sides of ramp and landings.
- Install new approx. 20' x 5' x 4" sidewalk at 1:20 slope over 6" compacted gravel, connecting new ramp to existing public sidewalk. Regrade side yard to meet new sloped sidewalk. **REFER TO PLANS FOR DETAIL!**

Bid amount \$ _____