

# Scope of Work Breakdown – 3361 Sixth Avenue

---

## Carpentry

- - Remove existing ramp decking, handrails, guards and posts.
- - Install new, P.T. decking, approx. 300 SF, over existing ramp framing.
- - Provide non-slip transition surface at material
- - Provide (2) new P.T. 2x6 posts on concrete footings at (2) locations on south side of existing ramp for new landing.
- See plans for details on 4" X 4" beams as they connect to 10" concrete sonotubes

## Masonry

- - Install an approx. 5'-0" x 5'-0" x 9", 1:12 sloped concrete landing where existing ramp meets existing sidewalk.

## Site Work

- - Remove existing chain link fence along front.
- - Provide non-slip ramp surface throughout, and non-slip transition surface at material transition between decking and concrete surfaces.
- - Provide new 10" diameter concrete sonotube footings, min. 4'-0" below grade, at (10) locations where existing posts do not bear on footings.
- - Provide new 1 1/2" black vinyl coated, aluminum graspable handrail and guards along both sides of ramp and existing stairs and platform.

**Total Bid \$**\_\_\_\_\_