



SCOPE OF WORK – 350 6th Ave Troy NY 12182 – Vinyl Sheet Flooring

Provide all labor, materials, equipment, disposal, and incidentals necessary to remove and replace approximately 200 square feet of basement flooring and subfloor.

- Remove and dispose of existing flooring and basement subfloor within the work area.
- Inspect exposed framing/substrate and notify Owner of any significant deterioration outside this scope.
- Furnish and install new 3/4-inch subfloor, properly fastened and prepared to provide a clean, smooth, level surface.
- Furnish and install approximately 200 square feet of San Marco Slate Stone Look, 10-mil waterproof vinyl sheet flooring, or approved equivalent.
- Install manufacturer-approved adhesive and properly fit, roll, seal, and finish flooring. Minimize seams where possible.
- Furnish and install necessary transition strips and reinstall or replace base trim as required.
- Remove all debris and leave the completed flooring clean, secure, smooth, and ready for use.

Contractor shall field-verify all dimensions and existing conditions prior to ordering materials. Price shall include all labor, materials, removal, subfloor replacement, flooring, adhesive, preparation, trim, transitions, disposal, cleanup, and incidentals necessary for a complete installation.

Slate Stone Look Vinyl Sheet Flooring





