



Scope of Work – Reconstruction of Brick Masonry Basement Wall at Stairway

854 Third Avenue – Troy, NY 12182

Scope of Work – Rebuild Brick Wall at Basement Stairway

Provide all labor, materials, equipment, shoring, and disposal necessary to remove and reconstruct the existing brick masonry wall on the left side of the basement stairway (going up).

- Temporarily shore and support all framing and structural components currently bearing on the existing brick wall before demolition.
- Carefully demolish and remove the existing deteriorated brick wall and dispose of debris.
- Rebuild the wall with sound salvaged brick and/or new brick of similar size and type.
- Provide appropriate mortar and construct the wall plumb, level, properly bonded, and adequately connected to the existing structure.
- Ensure the rebuilt wall provides proper bearing and support for the framing above before removing temporary shoring.
- Repair adjacent masonry disturbed by the work as necessary.
- Clean the work area and remove all construction debris.
- Contractor shall obtain required permits and complete the work in accordance with applicable building codes.
- Notify the Owner of significant concealed structural conditions requiring work beyond this scope before proceeding.

Please have quotes by 10.1.2026

Call 518.279.6631x3 to schedule a site visit



